

JAN 05 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Keweenaw

(County)

Located In:

Corner Code #

1. Public Land Survey

T 59 R 28 A-11

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

REGISTER'S OFFICE

County of Keweenaw } SS

Received for Record, the 13th

day of December A.D. 1999

at 1:00 o'clock P.M., and Recorded

in Liber 1 of LCR

on page 209

Julie Carlson, Deputy

Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

I, James M. Pardini, in a field survey on 9/21, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 1-13. Cell (1,1) contains a black dot.

A. Description of original monument and accessories and/or subsequent restoration:

(A-11) NW corner section 31 T59N-R28W. Section corner post set by William A. Burt in 1845.

U.S. Bearing Trees:

12" Cedar S50°E 3 lks

6" Cedar N40°W 6 lks

Subdivision of T59N-R28W by William Ives D.S. in 1845.

8" Cedar N47°E 27 lks

12" Cedar S35°E 2 lks

Ratified by Peer Group
In accordance with P.A. 345
Co. Rep. [Signature]
Date 12/7/99

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-11) Calumet and Hecla Mining Co. records indicate iron pipe set from Cedar BT marked 28W /w BT near bottom in 1949

59N

30

1 1/2" iron pipe replaced /w 1"x36" iron pipe and cemented in place 6" above ground in 1998.

Robert W. Crampton found and witnessed 1" iron pipe in 1999.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-11) Set 4" brass cap marked Keweenaw Co. Remonumentation Point on 1" iron pipe.

14" Cedar N78°W 28.77'

14" Cedar N06°W 19.60'

16" White Birch S35°E 18.74'

10" Cedar S25°W 16.87'

Original Cedar BT standing in fair condition /w blazes and scribe marks plainly visible.

Bears: N50°E 14" in diameter Dist 17.90'

Signed by James M. Pardini
Surveyor's Michigan License No. 32340

Date 12/7/99

