

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 15 PM 1 37

For corners in ROSS TWP.

KALAMAZOO (County) Located in: Corner Code #

1. Public Land Survey T 1 S 9 R W A-7
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

James J. Jones
CLERK-REGISTER

LIBER 1 PG 1228

Register of Deeds Stamp & File Number

I, Allen H. McMachen a field survey on July 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1880's - F. Hodgeman C.S. Placed Clay Tile Post during official Township Remonumentation.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found Clay Tile 4" Above Grade.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
11-17-94



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Found Clay Tile is accepted as a careful & faithful perpetuation of the original corner. Removed top section of Clay Tile and placed Standard Sleeve over existing bottom section of Tile.
 Accessories:

- Nail & Tab in 16" Hickory N. 05° E. 31.20'
- Nail & Tab in 16" Oak N. 77° E. 10.29'
- Nail & Tab in 24" Oak SOUTH 14.79'
- Nail & Tab in 10" Oak S. 65° W. 10.84'

Signed by Allen H. McMachen
 Surveyor's Michigan License No. 16935

Date 11/30/94