

SURVEY & REMONUMENTATION

1 AUG 06 1996
2 COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
'96 MAY 23 PM 1 47
Clerk-Register
[Signature]

For corners in Kalamazoo (County)
Ross Twp. Located In: Corner Code #

1. Public Land Survey	T <u>1</u> S. R <u>9</u> W.	<u>C-01</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

LIBER 2 PAGE 005
Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on May 2, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	13	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1826: United States Government Surveyors; intersected baseline 745 lks. West of 1/4 Section post. Set post at intersection common to Sections 5 and 6.
Wh. Oak 16" S. 48° W. 34 lks.
Wh. Oak 18" S. 49° E. 89 lks.
- 1883: F. Hodgman, County Surveyor; found stone with brick around and stake beside it. N. 1 3/4° W. 43 lks. from Maple bearing tree by Pratt. Bored 3 ft. in stake hole, put brick in bottom and 2 foot of earthen post over and marked.
Maple 12" N. 58° W. 90 1/3 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1967: Wilkins & Wheaton Engr. Co.; found 3" round tile, top broken.
Maple 24" S. 2° E. 26.35'
Maple 36" N. 59° W. 58.9'
Maple 24" S. 40° E. 42.25'
Northeast corner of House Southwest 84.46'

- 1996: Found 6" long carriage bolt over tile in gravel road, top of tile is broken.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
5-16-1996
R. E. S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-01: Northeast corner of Section 6, T. 1 S., R. 9 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on May 16, 1996, and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile, top broken, as set by F. Hodgman, County Survey in an 1883 remonumentation survey. Placed a remonumentation sleeve over tile.
PK Nail on South Side of 15" Hickory N. 64° E. 64.13'
PK Nail on East Side of 15" Walnut S. 32° E. 32.13'
PK Nail on North Side of 48" Catalpa S. 80° W. 76.11'
PK Nail on South Side of 48" Maple N. 50° W. 58.95'

Signed by *Robert E. Snell* Date 5-23-96
Surveyor's Michigan License No. 9734