

**SURVEY &
REMONUMENTATION**

FEB 18 1994

**LAND CORNER RECORDATION CERTIFICATE
COMMISSION**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kalamazoo

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>1</u> S R <u>9</u> W | <u>C-2</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
94 JUN 21 AM 8 56
Clerk - Register
James P. [Signature]
LIBER 1 PG 1088
Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on December 14, 19 93

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	7	8	9	10	11	12	13	14	15	16	17	18
3													
4	7	8	9	10	11	12	13	14	15	16	17	18	19
5													
6	18	17	16	15	14	13	12	11	10	9	8	7	6
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

A. Description of original monument and accessories and/or subsequent restoration:

East 1/4 Post established by United States Government Survey in 1826

- Wh. Oak 24" South 11°-E 60 Lks (39.6')
- Wh. Oak 9" North 59°-W 20 Lks (13.2')

1882-Ed Strong, County Surveyor-Reset stake and stones from one good U.S. Witness

1883-F. Hodgeman, County Surveyor-Found stake bored 3'. Put stone in bottom and 2' Earthen Post over.

- Wh. Oak 24" North 118 1/4 Lk (78.05')
- Wh. Oak 24" North 72 1/2-E 44 Lk (29.04')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original corner with accessories not recovered.

Found 1/2" x 6" rered over solid clay tile with "X" on top with accessories from previous survey and Kalamazoo County Surveyor records.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
12/16/93**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-2 East 1/4 Post Section 6, T. 1 S., R. 9 W., Ratified by Kalamazoo County Remonumentation Program Peer Group on December 16, 1993. Found 1/2" x 6" rered over solid clay tile as called for in previous Wilkins & Wheaton Engineering survey and 1883 Remonumentation by F. Hodgeman and is accepted as a careful and faithful perpetuation of the original corners position. Removed 1/2" x 6" iron rod and placed monument sleeve over solid clay tile with 1/2" x 6" iron rod over.

- PK Nail in North side 8" W. Cherry North 75°-E 13.92'
- PK Nail in North side 42" W. Cherry South 88°-W 59.95'
- PK Nail in West side 8" W. Cherry North 37°-30' West 9.5'
- PK Nail in West side 8" Elm South 08°-30'-E 32.44'

Signed by *Robert E. Snell* Date 1-20-94
Surveyor's Michigan License No. 9734