

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kalamazoo
(County)

Located In:

Corner Code #

Ross Section 17

1. Public Land Survey

T 1 S R 9 W

C-7

T _____ R _____

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Robert E. Snell, in a field survey on January 21, 19 94,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826-Original corner placed Post Cors. 17, 18, 19 and 20-U.S. Government Survey
Wh. Oak 18" North 28°-W 149 Lks (98.34')
Wh. Oak 14" South 75°-E 100 Lks (66')

1883-F. Hodgeman-County Surveyor-found stone with brick around it. Pointed out to me by Mr. Simpson and said by him to have been put in place of original stake. No bearing trees left. Bored down 3'. Put in one foot of broken brick and two foot earthen post over with stone around. Marked.

Hickory 12" West 12 Lks (7.92') Apple 10" South 60°-E± 17½ Lks (11.55')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3" clay tile with "X" on top and stone around.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-7 Southwest Corner Section 17, T. 1 S., R. 9 W., ratified by Kalamazoo County Remonumentation Program Peer Group on March 3, 1994. Found 3" round tile with "X" on top as called for in 1883 remonumentation survey by F. Hodgeman and is accepted as a careful and faithful perpetuation of the original corners position. Placed remonumentation sleeve over tile.

PK Nail in N side	30" Maple	East	109.36'
SW Cor Garage Foundation		S 60°-E	95.10'
PK Nail in W side	10" Locust	North	42.10'
PK Nail in E side	6" Maple	S 88°-W	24.67'

Signed by Robert E. Snell

Date 3-15-94

Surveyor's Michigan License No. 9734

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
94 MAR 15 PM 1 37
CLERK-REGISTER
LIBER 1 PG 1112
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
3-3-94