

**SURVEY & REMONUMENTATION**

7-  
2-

JUL 23 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2PAGE 124

For corners in Ross Twp.

Kalamazoo (County)	Located In:	Corner Code #
1. Public Land Survey	T1S R9W	C-08
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
97 APR 7 AM '97  
CLERK - REGISTER

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert E. Snell, in a field survey on March 14, 1994 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1826: United States Government Surveyors; set 1/4 Section post.  
Elm 7" S. 33° E. 32 lks.  
Elm 6" N. 02° W. 34 lks.
  - 1883: F. Hodgman, County Surveyor; "Found stake with stone around in swamp, set by me in 1873 in place of older stake. Correct by one U.S. bearing tree, then standing, now gone. Put 1 ft. of small stones with 2 foot earthen post over for corner and marked - Whitewood 16" S. 18¼° E. 148 lks."

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1970: Wilkins & Wheaton Engr. Co.; found tile in swamp 659.74' South of center line of Highway M-89. Tile in fence line East and 1.2' West of fence to South.
  - 1983: Wilkins & Wheaton Engr. Co.; found tile in swamp.
  - 1994: Found 3" round tile with "x" on top in swamp with several cut logs around tile all rotted off at surface.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP** 2-27-1997

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- C-08: East 1/4 post, Section 19, T. 1 S., R. 9 W.; ratified by the Kalamazoo County Remonumentation Program Peer Group on February 27, 1997 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile with "x" on top as placed by F. Hodgman, County Surveyor, in 1883 Remonumentation survey. Placed remonumentation sleeve over tile. East edge of swamp is East 86' ±.
- |                              |              |           |              |
|------------------------------|--------------|-----------|--------------|
| Nail in East Side            | 4" Maple     | N. 44° E. | 26.86'       |
| Nail in East Side            | 15" Oak      | North     | 49.07'       |
| Exist. Nail/Tab in East Side | 13" Tamarack | N. 06° W. | 27.88 (Dead) |
| Nail in West Side            | 4" Maple     | S. 10° W. | 40.58'       |
| Nail in West Side            | 4" Maple     | S. 50° E. | 10.56'       |

Signed by Robert E. Snell  
Surveyor's Michigan License No. 9734

Date 3-14-97