

1994 APR 28 AM 9 11

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

James J. Jones
 CLERK-REGISTER

LIBER 1 PG 1139

Register of Deeds Stamp & File Number

For corners in
 KALAMAZOO

(County)

Sec. 29, Ross Townshp

Located In:

Corner Code #

1. Public Land Survey	T 1 S R 9 W	C-9
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert E. Snell, in a field survey on January 31, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1826-Original corner established by U.S. Government Survey-Set Post, corner to Section 5, 20, 29 and 30.
 W. Oak 18" South 39° West 20 Lks
 W. Oak 9" North 72° East 54 Lks
 1873-F. Hodgeman, County Surveyor-found stake hole from stump of two witnesses, planted new stake 2½ links southeast of W. Oak-6" in dia.
 1883-F. Hodgeman, County Surveyor-found stake set by me on resurvey since years ago in place of original corner post. Set 2' earthen post with 1' of stone and coal underneath
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Wh. Oak 10' N 60° W 2 Lks
 Found 3" round tile broken and leaning.

R.E.S.
RATIFIED
 BY KALAMAZOO COUNTY
 REMONUMENTATION
 PEER GROUP
 3-3-94

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 C-9 Northeast Corner Section 29, T. 2 S., R. 9 W., ratified by Kalamazoo County Remonumentation Program Peer Group on March 3, 1994. Found 3" round tile as called for in remonumentation survey in 1883 by F. Hodgeman and is accepted as a careful and faithful perpetuation of the original corner's position. Removed top section leaning tile and found second tile. Placed remonumentation sleeve over 8" piece of original tile and placed over lower section of tile.
 PK Nail in West Side 11" Oak N 08°-W 50.62' CL 14" Oak S 50°-W 6.2'
 PK Nail in West Side 12' Oak N 34°-E 27.15'
 PK Nail in North Side 17" Oak S 72°-E 22.01'
 Found Nail in W. Side 8" Oak S 21°-E 17.84'

Signed by *Robert E. Snell* Date 4-27-94
 Surveyor's Michigan License No. 9734