

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

'94 APR 28 AM 9 12

For corners in

KALAMAZOO

(County)

Located In:

Corner Code #

Sec. 29, Ross Township

1. Public Land Survey

T 1 S R 9 W

C-10

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous

S _____ T _____ R _____

Property in Sec.

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

James J. Jones
 CLERK - REGISTER

LIBER 1 PG 1149

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on March 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826-Original corner established by U.S. Government Survey-Set $\frac{1}{4}$ Post.

- Wh. Oak 7" North 64° West 4 Lks
- Wh. Oak 7" South 24° East 22 Lks

1883-F.Hodgeman, County Surveyor-Found stake hole South 64° East, 4 Lks from U.S. Bearing Tree. Bored 3', put down first 1' earthen post then 1' of stone and 1' earthen post on top.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3" round tile, from 1972 LCRC witnesses.

R.E. Snell
RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 4-21-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-10 West $\frac{1}{4}$ Post Section 29, T. 1 S., R. 9 W., ratified by Kalamazoo County Remonumentation Program Peer Group on April 21, 1994. Found 3" Clay tile broken and leaning. Dug through 1' of stone and found second tile as called for in 1883 remonumentation survey by F.Hodgeman and is a careful and faithful perpetuation of the original corner's position. Placed 20" Harrison monument over lower tile.

- Found Nail (1972), Set PK Nail in 13" Cherry North 10° West 30.40'
- In South Side, Set PK Nail in 15" Oak East 41.20'
- Found Nail (1972), Set PK Nail in 40" Oak South 05° East 4.06'
- Set PK Nail in 18" Hickory South 85° West 8.78'
- Set PK Nail in 12" Hickory North 80° West 37.93'

Signed by *Robert E. Snell*

Date 4-27-94

Surveyor's Michigan License No. 9734