

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Ross Twp.  
Kalamazoo  
 (County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

- |                                       |   |            |   |            |             |
|---------------------------------------|---|------------|---|------------|-------------|
| 1. Public Land Survey                 | T | <u>1S.</u> | R | <u>9W.</u> | <u>C-11</u> |
|                                       | T | _____      | R | _____      | _____       |
|                                       | T | _____      | R | _____      | _____       |
|                                       | T | _____      | R | _____      | _____       |
| 2. Property Controlling in Section    | S | _____      | T | _____      | R           |
|                                       | S | _____      | T | _____      | R           |
| 3. Miscellaneous Property in Section  | S | _____      | T | _____      | R           |
|                                       | S | _____      | T | _____      | R           |
| 4. Lot No. _____, Recorded Plat _____ |   |            |   |            |             |
| 5. Private Claims _____               |   |            |   |            |             |

LIBER 2 PAGE 333  
 RECEIVED FOR RECORD  
 98 OCT 12 PM 1 29  
 STATE OF MICHIGAN  
 COUNTY OF KALAMAZOO  
 CLERK - REGISTER  
*Janice Brown*

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	6	5	4	3	2	1					
5												
6	18	17	16	15	14	13	12	11	10	9	8	7
7												
8	19	20	21	22	23	24	25	26	27	28	29	30
9												
10	30	29	28	27	26	25	24	23	22	21	20	19
11												
12	31	32	33	34	35	36	37	38	39	40	41	42
13												

I, Allen H. McMachen, in a field survey on February 3, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- |  |   |  |
|--|---|--|
| <u>1826</u> - John Mullett, D.S.<br>Over lake set post on N.W. margin for mean. post and also for corner to Sections 29, 30, 31 & 32, Wh. Oak 8" N. 80° W. 5 lks., Wh. Oak 6" S. 25° W. 18 lks.. | <u>1883</u> - F. Hodgman<br>"From one U.S. bearing tree ran N. 25° E. 18 lks. to old stake in the woods on margin of lake. Set 3' earthen post and marked Wh. Oak 10" N. 52½° E. 21 lks., Wh. Oak 16" N. 38¼° W. 68½ lks.." | <u>1904</u> - Ed Strong, C.S., "Found tile & one bearing tree good"<br><u>1911</u> - Ed Strong, C.S., "Found tile"<br><u>1953</u> - Sup. Plat of "Forrest Beach" is recorded. Plat shows Section corner as a "found tile". |
|--|---|--|

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found concrete plat monument and its position was verified by its relationship with 3 additional plat monuments. Removed plat monument and dug to depth of 4 feet finding no additional evidence of corner.

SURVEY &  
REMONUMENTATION

NOV 25 1998

SECTION

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP

2/19/98  
*R.E.S.*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Position of found concrete plat monument is accepted as the best available evidence of the position of the original corner. Placed 30" Harrison Monument in place of found concrete plat monument, Accessories:

- Nail in Northwestern side of 20" Ash N. 45° E. 24.20'
- Nail in Westerly side of 8" Ash S. 05° E. 9.35'
- Nail in Northerly side of 20" Maple West 11.5'
- A S.E. corner of house S. 25° W. 20.40'



Signed by *Allen H. McMachen*  
 Surveyor's Michigan License No. 16935

Date 9/24/98