

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1978

APR 28 AM 9 11

James J. [Signature]
 CLERK-REGISTER

LIBER 1 PG 1140

Register of Deeds Stamp & File Number

For corners in

KALAMAZOO

(County)

Sec. 32, Ross Township

Located In:

Corner Code #

- | | | | | | | | |
|------------------------------------|---|---|---|---|---|---|------|
| 1. Public Land Survey | T | 1 | S | R | 9 | W | C-12 |
| | T | | R | | | | |
| | T | | R | | | | |
| | T | | R | | | | |
| 2. Property Controlling in Section | S | | T | | R | | |
| | S | | T | | R | | |
| 3. Miscellaneous Property in Sec. | S | | T | | R | | |
| | S | | T | | R | | |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert E. Snell, in a field survey on February 9, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1826-Original corner established by U.S. Government Survey-Set $\frac{1}{4}$ Post.
 - Wh. Oak 9" South 21° West 9 Lks
 - Wh. Oak 14" South 87° East 30 Lks
 - 1883-F. Hodgeman, County Surveyor-from stump of U.S. Bearing Tree, ran North 87° West, 30 Lks and at the interseciton of fences. Set 3' earthen post.
 - Hickory 4" South 50° West 1½ Lks
 - Hickory 10' North 22° East 18 Lks

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- Found 3" round clay tile with "X" on top-Acro 1969 Witness. Approximately 4' North of East and West fence
 - 12" Black Cherry North 14.95' (fd Hickory)
 - 20" Oak North 40° East 59.90'

[Signature]
 RATIFIED
 BY KALAMAZOO COUNTY
 REMONUMENTATION
 PEER GROUP
 3-3-94

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- C-12 East $\frac{1}{4}$ Post, Section 31, T. 1 S., R. 9 W., ratified by Kalamazoo County Remonumentation Program Peer Group on March 3, 1994. Found 3" clay tile as called for in 1883 remonumentation survey by F. Hodgeman and is accepted as a careful and faithful perpetuation of the original corner's position. Placed remonumentation sleeve over tile.

PK Nail in East Side	18" Hickory	North	14.80'	CL of Drive South	19'±
PK Nail in West Side	12" W. Cherry	S 46°-E	5.97'	CL of Drive West	17'±
PK Nail in West Side	15" Hickory	S 08°-E	26.35'		
CL Circular PVC Telephone Pedestal		S 28°-W	3.70'		

Signed by *Robert E. Snell* Date 4-27-94
 Surveyor's Michigan License No. 9734