

'94 APR 28 AM 9 11

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALAMAZOO
(County)

Located In:

Corner Code #

Sec. 31, Ross Township

1. Public Land Survey

T 1 S R 9 W

C-13

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
 in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
 Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Jeanette Jones
 CLERK-REGISTER

LIBER 1 PG 1142

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on February 9, 19 94,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1825-Original corner established by U.S. Government Survey-Set Post, corner to Sections 31 and 32

Wh. Oak 16" North 61° East 36 Lks

Wh. Oak 17' North 82° West 20 Lks

1883-F. Hodgeman, County Surveyor-found old stake hole 195 Lks East of Charleston Corner at intersection of fences. No Bearing Trees, Planted 3' earthen post.

Wh. Oak 36" North 05° East 8½ Lks

Wh. Oak 28" South 59° East 69 Lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found broken tile, 3" Diameter, 0.8' South of Fence, East, West, and North.

R. E. Snell
RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 3-3-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13 Southeast Corner Section 31, T. 1 S., R. 9 W., ratified by Kalamazoo County Remonumentation Program Peer Group on March 3, 1994. Found 3" diameter clay tile with top broken Tile called for in 1883 remonumentation survey by F. Hodgeman and is accepted as a careful and faithful perpetuation of the original corner's position. Removed broken tile and placed remonumentation sleeve over a 8" piece of tile and placed over lower tile.

PK Nail in South Side 15" Hickory South 60° East 14.57'

PK Nail in West Side 15" Hickory South 20° East 23.53'

PK Nail in South Side 15" Hickory West 22.57'

PK Nail in West Side 12" Oak North 02° West 36.38'

Signed by *Robert E. Snell*

Date 4-27-94

Surveyor's Michigan License No. 9734