

**SURVEY &
REMONUMENTATION**

FEB 18 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'93 DEC 29 AM 10 31

For corners in

Kalamazoo
(County)

Located In:

Corner Code #:

Ross Twp.

- | | | |
|------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>15</u> R <u>9W</u> | <u>D-5</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

James E. Young
CLERK-REGISTER

LIBER 1 PG 1048

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, James E. Boynton, in a field survey on December 1, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5		●											
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original post set by U.S. Government Deputy Surveyor John Mullitt in 1826. Corner remonumented in 1883 by F. Hodgeman, set standard tile, accessories; W.O. 4 N. 37E. 18; Y.O. N. 64W. 42. tile found in 1902 by E. Strong. Tile found in 1952 by Wilkins & Wheaton, witnesses taken.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found tile from 1952 witnesses: N.E. Corner of garage S.O.W. 11.4'; N.E. Corner house S. 85W. 36.4'; S.E. Corner concrete walk N.W. 26.94'.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
12-16-93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found and accepted tile as carefull and faithful perpetuation of original post. Set standard sleeve over tile, new witnesses: P.P. N. 60°E. 33.15' to nail; 24" Oak East 48.52' to nail; T.P. S. 30°E. 60.50' to nail; 36" Oak N. 60°W. 28.89' to nail.

Signed by James E. Boynton Date 12-9-93

Surveyor's Michigan License No. 29239