

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kalamazoo
(County)

Located In:

Corner Code #

Ross Section 29

- | | | |
|------------------------------------|-------------------------|-------|
| 1. Public Land Survey | T 1 S R 9 W | D-11 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert E. Snell, in a field survey on January 5, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by U.S. Government Survey in 1826. Set Post.

- Blk. Oak 18" South 17°-E 21 Lks (13.86')
- Wh. Oak 12" North 21°-E 46 Lks (30.36')

1883-F. Hodgeman County Surveyor-ran South 21°-W, 46 Lks from government stump to stake hole--marks of stump, South 17°-E 21 Lks, removed. Bored three feet and set earthen post.

- Wh. Oak 24" North 07°-E 75 Lks (49.5')
- Wh. Oak 24' North 70°-W 69½ Lks (45.87')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found solid clay tile with "X" on top from 1967 survey with stone and brick around at surface.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-11 South 1/4 post Section 29, T. 1 S., R. 9 W., ratified by Kalamazoo Remonumentation Program Peer Group on January 20, 1994. Found solid clay tile with "X" on top as called for in 1883 remonumentation by F. Hodgeman and is accepted as a careful and faithful perpetuation of the original corners position. Removed stone and brick, placed remonumentaiton sleeve over tile and replaced stone and brick around.

- PK Nail in N side 15" Hickory S 35°-E 7.03'
- Nail/Tab in N side 24" Oak S 82°-W 17.68'
- Nail in W side 15' W.Cherry N 45°-W 14.03'
- PK Nail in W side 24"&15" Oak N 25°-E 41.27'
- SW cor of concrete slab (well Pit) N 60°-E 101.6'

Signed by Robert E. Snell
 Surveyor's Michigan License No. 9734

Date 3-15-94

CLERK - REGISTER

Janet [Signature]

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 '94 MAR 15 PM 1 37

LIBER 1 PG 1111
 Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 1-20-94