

7-  
2-  
SURVEY &  
REMONUMENTATION

AUG 22 1995

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

Kalamazoo (County) Located In: Corner Code #

Ross Township  
1. Public Land Survey T 1 S R 9 W D-13  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
95 JUN 6 AM 9 05  
CLERK - REGISTER  
*[Signature]*

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

LIBER 1 11303

I, Robert E. Snell, in a field survey on September 19, 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1825: U.S. Government Survey; Set 1/4 Section Post.  
W. Oak 9" North 40 1/2° East 54 Lks  
W. Oak 9" North 47 1/2° West 82 Lks

1883: F. Hodgman, County Surveyor; All traces of bearing trees gone. Sighted the Town Line East and West and in that line in range with fences North. Found stake hole with rotten wood put 1' of stone in bottom and 2' earthen post over and marked.  
Hickory 10" North 58° East 90 1/2 Lks  
Hickory 10" South 64 3/4° East 96 1/2 Lks

1956: Wilkins & Wheaton Engineering; Found tile. 18" Hickory N 89° W 77.5' In fence line to N  
B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: 6" Oak S 79° E 96.0'  
P/P #416 N 52° W 75.7'

1994: Found monument box on South edge of concrete road. Found 1/2" x 12" iron inside. Below iron, found second iron (1/2" x 24"). Found tile 24" below surface along side of 24" iron.

THIS L.C.R.C. IS RECORDED TO  
CORRECT ERRORS IN L.C.R.C.  
LIBER 1, PAGE 1193 IDENTIFIED  
IN ERROR AS E-13.

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
11-17-94  
*[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 South 1/4 Section 32, T. 1 S., R. 9 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on November 17, 1994. Found 3" round tile 24" below surface as called for in 1883 remonumentation by F. Hodgman and is accepted as a careful and faithful perpetuation of the original corner's position. Placed 20" Harrison monument over tile in existing monument box.

PK Nail in North Side	14" Oak	S 60° W 103.41'	Monument Box on S.Edge
PK Nail in East Side	12" Cherry	North 54.35'	Concrete Pavement
Exist. Nail/Tab in North Side	Telephone Pole	S 42° E 33.01'	In line w/fence to North
PK Nail in Northeast Side	Power Pole	N 50° E 166.83'	Fence to Southwest 88'

Signed by *Robert E. Snell* Date 3-7-95  
Surveyor's Michigan License No. 9734