

2  
8

**SURVEY & REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Kalamazoo  
(County)

**AUG 22 1995**

Located In:

Corner Code #

Ross Township

**COMMISSION**

1. Public Land Survey	T <u>1</u> S R <u>9</u> W	<u>E-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
 COUNTY OF KALAMAZOO  
 RECEIVED FOR RECORD  
 '95 JUN 6 AM 9 05  
 CLERK - REGISTER

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims LIBER 1 1305

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert E. Snell, in a field survey on November 8, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1826: United States Government Survey; intersected base line, 725 Lks West of 1/4 Section Post. Set Post at intersection corner to Sections 4 and 5.

Bl. Oak 15" South 22° East 49 Lks  
 Wh. Oak 16" South 42° West 83 Lks

1883: F. Hodgman, County Surveyor; Found stake Northwest, 87 Lks from Hickory bearing tree by Pratt. Bored 3', put stone in bottom and 2' earthen post over.

Hickory 10" South 65 1/4° West 144 Lks  
 Hickory 7" South 39° East 87 Lks

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1920 (CIRA.) 10" Elm North 20° East 17.9'  
 Cement Rod Southwest 36.0'  
 24" Bass North 40° West 39.3'

1994: Found 3" round tile 1.3' below surface. Took witnesses.

**RATIFIED  
 BY KALAMAZOO COUNTY  
 REMONUMENTATION  
 PEER GROUP  
 12-15-94**

*R.E.S.*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

E-1 Northwest Corner Section 4, T. 1 S., R. 9 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on December 15, 1994 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3' round tile 1.3' below surface of the road, the tile was set by F. Hodgman in 1883 remonumentation survey. Tile was removed during road construction. Placed a 20" Harrison monument in monument box from witnesses.

Exist. Nail/Tab in East Side Power Pole North 20° East 37.37'  
 Exist. Nail/Tab in Southwest Side 27" Hickory South 50° East 86.15'  
 PK Nail in East Side Power Pole South 20° West 74.66'  
 PK Nail in North Side 15" Oak South 70° West 87.41'

Signed by Robert E. Snell Date 6-02-95  
 Surveyor's Michigan License No. 9734