

7-
2- SURVEY &
REMONUMENTATION
2423

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

AUG 22 1995

For corners in

Kalamazoo **COMMISSION** Located In: _____ Corner Code # _____
(County)

Ross Township

- | | | |
|------------------------------------|---------------------------|-------|
| 1. Public Land Survey | T <u>1</u> S R <u>9</u> W | E-2 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

LIBER 1 1307

I, Robert E. Snell, in a field survey on October 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules hereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826: United States Government Survey; Set 1/4 Section Post.

Wh. Oak	40"	South	10°	West	55 Lks
Wh. Oak	18"	North	15°	West	102 Lks

1883: F. Hodgman, County Surveyor; Found a brick set for Corner South 80° West 53 1/3 Lks from Wh. Oak Bearing Tree by Pratt. Bored 3', put brick in bottom and 2' earthen post over.

Hickory	12"	North	42°	East	77 1/3 Lks
Wh. Oak	12"	North	81°	East	53 Lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found 3" round tile 20" below surface of road.

SATISFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
12-15-94 *R.E.S.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-2 West 1/4 Post Section 4, T. 1 S., R. 9 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on December 15, 1994 and is accepted as a careful and faithful position of the original corner. Found a 3" round tile with "X" on top, 20" below surface as called for in 1883 remonumentation survey by F. Hodgman. Placed a 20" Harrison monument in monument box over tile.

	1/2" Iron Rod	South 82° East	49.96'
Exist. Nail/Tab in West Side	20" Hickory	North 24° East	102.55'
Exist. Nail/Tab in North Side	Power Pole	North 54° East	77.37'
Notch in top of Northeast Bolt on	Light Pole Base	South 36° West	69.49'
PK Nail in North Side	Fence Post	West	35.24'

Signed by *Robert E. Snell* Date 6-5-95

Surveyor's Michigan License No. 9734

