

'94 APR 28 AM 9 11

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALAMAZOO
 (County)

Located In:

Corner Code #

- Sec. 29, Ross Township
1. Public Land Survey T 1 S R 9 W E-9
 T _____ R _____
 T _____ R _____
 T _____ R _____
 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

James E. Snell
 CLERK-REGISTER

LIBER 1 PG 1141

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on March 3, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1826-Original corner established by U. S. Government Survey-Set Post to corner of Sections 20, 21, 28 & 29
 Wh. Oak 10" South 07° East 66 Lks
 Wh. Oak 14" North 54° West 46 Lks
 - 1883-F.Hodgeman, County Surveyor-found stake hole South 54° East, 46 Lks from stump of U.S. Bearing Tree. Bored 3', filled the bottom with stone and iron and put 2' earthen post over.
 Wh. Oak 20" North 74° West 118½ Lks
 Wh. Oak 5" North 07½° West 1 Lk
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 3" clay tile with "X" on top from LCRC witness-1976.
 6" down.

- 24" Hickory South 85° West 27.80'
- 24" Wh. Oak North 30° West 24.90'
- 8" Hickory South 10° East 43.50'

R. E. Snell
RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 3-17-94

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 E-9 Northeast Corner Section 29, T. 1 S., R. 9 W., ratified by Kalamazoo County Remonumentation Program Peer Group on March 17, 1994. Found 3" clay tile with "X" on top, down about 6" as called for in 1883 remonumentation survey by F. Hodgeman and is accepted as a careful and faithful perpetuation of the original corner's position. Placed remonumentation sleeve over tile.

- Spike in East Side 24" Oak North 30° West 27.28'
- Spike in East Side 8" Hickory South 10° East 24.77'
- Spike in South Side 14" Db1. Sass. East 28.13'
- East Face RR Tie Fence Post West 1.46'

Signed by *Robert E. Snell* Date 4-27-94
 Surveyor's Michigan License No. 9734