

'94 APR 28 AM 9 11

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALAMAZOO  
(County)

Located In:

Corner Code ##

1. Sec. 29, Ross  
Public Land Survey

T 1 S R 9 W

E-11

2. Property Controlling  
 in Section

S \_\_\_ T \_\_\_ R \_\_\_  
 S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous  
 Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_  
 S \_\_\_ T \_\_\_ R \_\_\_

*James J. [Signature]*

CLERK - REGISTER

LIBER 1 PG 1143

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Robert E. Snell, in a field survey on March 3, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1826-Original Corner established by U.S. Government Survey-Set Post to corners 28, 29, 32 & 33

Wh. Oak 12" South 41 Lks  
 Wh. Oak 15" North 58° West 10 Lks

1883-F. Hodgeman, County Surveyor-Ran South 05° East, 10 Lks from stump of U.S. Bearing Tree to stake standing. Bored 3' put 1' earthen post then 1' of stone and 1' earthen post in top with stone around.

Red Oak 8" North 30½° West 33 Lks  
 Red Oak 24" North 78½° East 46 Lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3" tile with "X" on top with stone around

*R. E. Snell*  
**RATIFIED**  
 BY KALAMAZOO COUNTY  
 REMONUMENTATION  
 PEER GROUP  
 3-17-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-11 Southeast Corner Section 29, T. 1 S., R. 9 W., ratified by Kalamazoo County Remonumentation Program Peer Group on March 17, 1994. Found 3" clay tile near surface with stone around as called for in 1883 remonumentation survey by F. Hodgeman and is accepted as a careful and faithful perpetuation of the original corner's position. Placed a remonumentation sleeve over top of tile.

Spike in East Side 18" Hickory South 20° East 15.70'  
 Spike in East Side 15" Hickory South 10° West 7.33'  
 Spike in East Side 24" Hickory North 10° East 10.70'  
 Southeast Corner of RR Tie Fence Corner North 10° West 0.70'

Signed by *Robert E. Snell*  
 Surveyor's Michigan License No. 9734

Date 4-27-94