

**SURVEY & REMONUMENTATION**

APR 27 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

94 DEC 6 PM 3 56

For corners in  
Kalamazoo  
(County)

Located In: Corner Code #

Ross Township				
1. Public Land Survey	T	1	S	R 9 W
	T		R	
	T		R	
	T		R	
	T		R	
2. Property Controlling in Section	S		T	R
	S		T	R
3. Miscellaneous Property in Sec.	S		T	R
	S		T	R

E-13

*James J. [Signature]*  
CLERK-REGISTER

LIBER 1 PG 1193

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert E. Snell, in a field survey on September 19, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1825: U.S. Government Survey; Set Post, corner to Sections 32 and 33

W. Oak 17" North 14° East 53 Lks  
W. Oak 9" North 52° West 76 Lks

1883: F. Hodgeman, County Surveyor; Found stake and stone of resurvey. No witness trees. Charleston corner 95 Lks West. Set 3' earthen post with stones around. No trees convenient for witness.

1956: Wilkins & Wheaton Engineering; Found tile. 18" Hickory N 89° W 77.5' In fence line to N  
6" Oak S 79° E 96.0' P/P #416 N 52° W 75.7'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: P/P #417 N 75° E 88.0'

1994: Found monument box on South edge of concrete road. Found 1/2" x 12" iron inside. Below iron, found second iron (1/2" x 24"). Found tile 24" below surface along side of 24" iron.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
11/17/94 *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13 Southeast Corner Section 32, T. 1 S., R. 9 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on November 17, 1994. Found 3" round tile 24" below surface as called for in 1883 remonumentation by F. Hodgeman and is accepted as a careful and faithful perpetuation of the original corner's position. Placed 20" Harrison monument over tile in existing monument box.

PK Nail in North Side 14" Oak S 60° W 103.41' Monument Box on S.Edge  
PK Nail in East Side 12" Cherry North 54.35' Concrete Pavement  
Exist. Nail/Tab in North Side Telephone Pole S 42° E 33.01' In line w/fence to North  
PK Nail in Northeast Side Power Pole N 50° E 166.83' Fence to Southwest 88'

Signed by *[Signature]*  
Surveyor's Michigan License No. 9734

Date 12-06-94