

SURVEY & REMONUMENTATION

1
2
SEP 14 1998

LIBER 2 PAGE 299

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION Ross Twp.
For corners in Kalamazoo
(County)

Located In: Corner Code #

1. Public Land Survey	T	1S.	R	9W.	F-11
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
98 PMR 26 PM 3 28
CLERK - REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Allen H. McMachen, in a field survey on February 3, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	9	10	11	12						
5												
6	15	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	28	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1826 - John Mullett, D.S.
Set quarter Section post, Wh. Oak 18" S. 47° E. 21 lks.,
Wh. Oak 18" N. 70° W. 21 lks..

1883 - F. Hodgman, C.S.
"Found stake hole at intersection of fences correct by stumps of (2) U.S. bearing trees. Bored 3' put stone, coal and small stone in the bottom and 2' earthen post over and marked Wh. Oak 8" N. 42° E. 14 lks., Wh. Oak 12" S. 83¼° W. 46½ lks..

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found clay tile in North and South fence line and 1.2' South of East and West fence line. Top of tile was 1" below grade.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
2-19-1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found clay tile is accepted a careful and faithful perpetuation of the position of the original corner. Placed Standard Sleeve over found clay tile, Accessories:

- Nail in S.E. side of 16" Oak N. 65° E. 27.78'
- Nail in S.W. side of 42" Cherry S. 25° E. 21.60'
- Nail in Southerly side of 30" Cherry West 34.06'
- Nail in Northeast side of 44" Cherry N. 40° W. 18.90'



Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 2/24/98