

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

'94 MAR 17 PM 3 39

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **ROSS TWP.**

**KALAMAZOO**  
(County)

Located In:

Corner Code #

- |                                    |                           |            |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey              | T <u>1</u> S R <u>9</u> W | <u>G-8</u> |
|                                    | T ___ R ___               | _____      |
|                                    | T ___ R ___               | _____      |
|                                    | T ___ R ___               | _____      |
| 2. Property Controlling in Section | S ___ T ___ R ___         | _____      |
|                                    | S ___ T ___ R ___         | _____      |
| 3. Miscellaneous Property in Sec.  | S ___ T ___ R ___         | _____      |
|                                    | S ___ T ___ R ___         | _____      |

*James Ferguson*  
CLERK-REGISTER

LIBER **1 PG 1120**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**Allen H. McMachen** in a field survey on January 31, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
1880's - F. Hodgeman C.S. Placed Clay Tile post during official Township Remonumentation.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found Clay Tile at surface

*R.S.F.*  
**RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
3-3-94**



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Found Clay Tile is accepted as a careful and faithful perpetuation of the original corner. Place Standard Sleeve over existing Clay Tile, accessories:

- 3" Dia. Steel pipe (10' high) NORTH 0.4'
- Nail & Tab in Southwest face 8" Oak N. 22 deg. W. 52.45'
- Nail & Tab in Southwest face 10" Oak N. 70 deg. W. 110.20'
- Nail & Tab in South face 10" Pine S. 80 deg. W. 149.32'
- Northwest corner of Consumers Power Co. Electric Transmission Tower N.75 deg. E. 74.7'

Signed by Allen H. McMachen Date 3/15/94  
Surveyor's Michigan License No. 16935