

REMONUMENTATION

AUG 06 1996

1 COMMISSION  
2

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Kalamazoo Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

Ross Twp.

1. Public Land Survey	T <u>1</u> S. R <u>9</u> W.	<u>G-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

CLERK - REGISTER  
*[Signature]*

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
96 MAY 23 PM 1 47

LIBER 2 PAGE 008

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert E. Snell, in a field survey on April 24, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1826: United States Government Surveyors; set 1/4 Section post.

Wh. Oak 12" S. 64° E. 18 lks.  
Wh. Oak 10" N. 9° W. 20 lks.

1883: F. Hodgman, County Surveyor; found 1½" lead pipe 2' long set by Pratt at a point N. 64½° W. 42 lks. from Wh. Oak bearing tree. Drove pipe down and set 2 foot earthen post over it and marked.

Pine 6" N. 75° E. 65½ lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1964: Wilkins & Wheaton Engr. Co.; found tile West side of road.

Pine 20" N. 75° E. 43.90'  
Hickory 18" N. 20° E. 86.70'  
North end of stone wall 26.2'

1996: Found ½" x 12" long iron bar from witnesses over tile 36" deep, top broken, stone around tile.

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
5-16-1996  
*[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-10: West 1/4 post Section 27, T. 1 S., R. 9 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on May 16, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile with top broken as set by F. Hodgman, County Surveyor in 1883 remonumentation survey. Placed 20" Harrison Monument in monument box over-tile.

PK Nail on West Side of 32" Hickory N. 22° E. 87.15'  
PK Nail on South Side of 34" Pine N. 76° E. 43.03'  
PK Nail on South Side of 30" Oak S. 60° E. 48.38'  
PK Nail on North Side of Telephone Pole N. 80° W. 24.98'

Signed by *[Signature]*  
Surveyor's Michigan License No. 9734

Date 5-23-96