

**SURVEY & REMONUMENTATION**

SEP 14 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER

2 PAGE 313

CLERK - REGISTER

*Janice J. Johnson*

1998 SEP 3 PM 3 25

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

For corners in Ross Twp.

| Kalamazoo<br>(County)              | Located In: | Corner Code # |
|------------------------------------|-------------|---------------|
| 1. Public Land Survey              | T 1S R 9W   | G-11          |
|                                    | T R         |               |
|                                    | T R         |               |
|                                    | T R         |               |
| 2. Property Controlling in Section | S T R       |               |
|                                    | S T R       |               |
| 3. Miscellaneous Property in Sec.  | S T R       |               |
|                                    | S T R       |               |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert E. Snell, in a field survey on March 26 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    |   |    |   |    |   |    |   |    |   |    |   |    |   |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1  | A | B  | C | D  | E | F  | G | H  | I | J  | K | L  | M |
| 2  |   | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  |   | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  |   | 16 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 8  |   | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 |   | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 |   | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |   |    |   |    |   |    |   |    |   |    |   |    |   |

A. Description of original monument and accessories and/or subsequent restoration:

- 1826: United States Government Surveyors; set post corner to Sections 27, 28, 33 and 34.  
White Oak 14" S. 44° E. 48 lks.  
White Oak 18" N. 16° E. 68 lks.
- 1883: F. Hodgman, County Surveyor; "Found old stake hole N. 79½° E. 18 lks. from stump of Black Oak 6" of Pratt's survey. Bored 3' put stone, coal and small stones in the bottom and 2 ft. earthen post over and marked Y. Oak 6" N. 24° W. 87½ lks., White Oak 6" N. 81½° W. 81 lks."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1967: Wilkins & Wheaton Engr. Co.; found tile, under large stone. Oak N. 75° W. (large blaze) 22.0', in East and West fence.
- 1998: Found 3" round tile with "x" on top 6" below surface, along south side of large stone. Noted: 12" Dead Apple N. 40° E. 4.8', 1' South of East and West fence line.

**RATIFIED**  
**BY KALAMAZOO COUNTY**  
**REMONUMENTATION**  
**PEER GROUP**  
4-16-1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-11: Southwest corner, Section 27, T. 1 S., R. 9 W., ratified on April 16, 1998 by the Kalamazoo County Remonumentation Program Peer Group and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile with "x" on top 6" below surface and along side of a large stone. Tile was placed by F. Hodgman, County Surveyor in a 1883 Remonumentation survey. Placed Remonumentation sleeve over tile.

|                       |           |           |        |
|-----------------------|-----------|-----------|--------|
| PK Nail in North Side | 8" Oak    | S. 46° E. | 30.83' |
| PK Nail in South Side | 22" Oak   | N. 60° W. | 20.45' |
| PK Nail in South Side | 10" Oak   | N. 44° W. | 18.20' |
| PK Nail in South Side | 12" Maple | N. 60° E. | 33.70' |

Signed by Robert E. Snell  
Surveyor's Michigan License No. 9734

Date 9-2-98