

**SURVEY & REMONUMENTATION**

APR 27 1995

LIBER

1 PG 1194

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kalamazoo

(County)

Ross Township

1. Public Land Survey

Located In:

Corner Code #

T 1 S R 9 W

G-13

T

R

T

R

T

R

2. Property Controlling in Section

S

T

R

S

T

R

3. Miscellaneous Property in Sec.

S

T

R

S

T

R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

CLERK - REGISTER  
*[Signature]*

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
94 DEC 9 AM 9 24

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on September 23, 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1825: U.S. Government Survey; Set Post to Sections 33 and 34 from which;

W. Oak 15" North 31° East 82 Lks  
W. Oak 16" North 47½° West 78 Lks

1869: F. Hodgeman, County Surveyor; Found stake at Southwest Corner of Section 34, T. 1 S., R. 9 W. and set an iron stake deep in the earth for the corner and placed a stone 2 feet long above it with the flat side to the West next (to) the stake. No witness.

1883: F. Hodgeman, County Surveyor; Found iron bar and large stone of former survey, 29 Lks East of Corner (to) Sections 3 & 4. Set 1' earthen post on top of iron bar on West side of stone, leaving stone in place.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1974: Greg Smith, LCRC Liber 1, Page 493; Found round tile with distressed top and cross with hole in center.

Southeast Corner House Foundation (314 Lincoln) North 35° West 39.20'  
Nail/Tab in Northeast Side 48" W. Cherry (1' up) South 50° East 98.48'  
Nail/Tab in North Side Power Pole with Streelight South 80° East 91.22'

Don Gilcrest, LCRC Liber 1, Page 569; Tile at South base of dead Oak tree in line with fence to West  
Fence Post West 18.32'  
Fence Post South 66.94'

1994: Found 3" round tile, 22" deep, in base of Mulberry tree. A 3/4" x 3" iron was 0.3' North and 0.20' East of tile.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 Southeast Corner Section 33, T. 1 S., R. 9 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on November 17, 1994. Found 3" round tile (22" below surface) as called for in 1883 remonumentation survey by F. Hodgeman and is accepted as a careful and faithful perpetuation of the original corner's position. Palced a 20" Harrison monument over tile.

Southeast Corner of House Foundation North 32° West 39.04'  
Southwest Corner of House Foundation North 50° West 55.96'  
PK Nail in East Side 12" Maple North 78° West 31.24'  
PK Nail in Railroad Tie Fence Post Cor. South 28° East 14.12'  
Traveled CL Lincoln Street East 34.0'

Signed by *Robert E. Snell*

Date 12-9-94

Surveyor's Michigan License No. 9734