

SURVEY & REMONUMENTATION

1 AUG 06 1996

2 COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Kalamazoo Located In: _____ Corner Code # _____
 (County)
Ross Township

1. Public Land Survey T1 S. R9 W. I-01
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Section S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 '96 MAY 23 PM 1 48
 LIBER 2PAGE 010
 Register of Deeds Stamp & File Number

CLERK - REGISTER
[Signature]

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert E. Snell, in a field survey on May 2, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1826: United States Government Surveyors; intersected baseline 745 lks. West of 1/4 Section post. Set post at intersection common to Sections 2 and 3.
 Wh. Ash S. 26° W. 12 lks.
 Sugar 7" S. 27½° E. 32 lks.
- 1883: F. Hodgman, County Surveyor; found stake and stone of former survey. Bored 3 ft. put stone in bottom and 2 foot earthen post over and noted without marks.
 Blk. Walnut 6" West 132 lks.
 Blk. Walnut 4" S. 59° E. 123 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1957: Wilkins & Wheaton Engr. Co.; found tile.
 Southwest corner of House Northwest 61.36'
 Southeast corner of House Northeast 62.22'
 Centerline 30" Elm West 17.2'
 Centerline 36" Elm Northeast 26.0'

1996: Found 3" round tile 24" deep with cross on top with stones around tile.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 5-16-1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-01: Northeast corner Section 3, T. 1 S., R. 9 W.; Ratified by the Kalamazoo County Remonumentation Program Peer Group on May 16, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile as set by F. Hodgman, County Surveyor in an 1883 remonumentation survey. Placed 20" Harrison Monument over tile in monument box.
 Southwest corner of Brick House N. 10° W. 61.42'
 Southeast corner of Brick House N. 20° E. 62.30'
 Southeast corner of Concrete Block Garage N. 60° W. 18.60'
 PK Nail on West Side of 15" Walnut S. 10° W. 51.79'

Signed by *Robert E. Snell* Date 5-23-96