

**SURVEY & REMONUMENTATION**

LIBER

1 PG 1213

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

APR 27 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

DEC 15 PM 1 36

For corners in ROSS TWP.

KALAMAZOO  
(County)

Located in:

Corner Code II

- |                                    |                         |            |
|------------------------------------|-------------------------|------------|
| 1. Public Land Survey              | T <u>1S</u> R <u>9W</u> | <u>I-6</u> |
|                                    | T _____ R _____         | _____      |
|                                    | T _____ R _____         | _____      |
|                                    | T _____ R _____         | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____      |
|                                    | S _____ T _____ R _____ | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ | _____      |
|                                    | S _____ T _____ R _____ | _____      |

*James J. Jones*  
CLERK-REGISTER

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Allen H. McMachen a field survey on March 18, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1880's - F. Hodgeman placed Clay Tile post during official Township Remonumentation.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1991 - Found  $\frac{1}{2}$ " iron rod over Clay Tile, removed iron and Tile and replaced with 4" diameter, 36" long concrete monument (Northeast corner of "Stoney Lake Hills No. 2", L. 36 of Plats, Page 9, Kal. Co. Rec.)

RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
1/20/94  
*R. E. U.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found concrete monument is accepted as careful and faithful perpetuation of the original corner. Removed Concrete Monument and replaced with Harrison Monument, accessories:

- "PK" Nail in North face of 5" Oak S. 85 deg. E. 13.78'
- "PK" Nail in East face of 18" Oak S. 25 deg. W. 17.12'
- "PK" Nail in North face of 20" Oak S. 75 deg. W. 17.38'
- $\frac{1}{2}$ " Iron Rod S. 01 deg. E. 218.00'

Signed by Allen H. McMachen  
Surveyor's Michigan License No. 16935

Date 4/5/94