

2

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
'94 MAR 17 PM 3 39

For corners in ROSS TWP.

KALAMAZOO <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 1 S R 9 W	K-4
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Jamett Young
CLERK-REGISTER

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy B. Ligman, in a field survey on January 24, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1883 - F. Hodgeman C.S. Placed Clay Tile post during official Township Remonumentation.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found Clay Tile in marsh at intersection of North-South and East-West fence line remnants

Randy B. Ligman
**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
3-3-94**



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Found Clay Tile is accepted as a careful and faithful perpetuation of the original corner. Placed Standard Sleeve over existing Clay Tile and placed "T" fence post next to sleeve, accessories:

- | | |
|---------------------------------|------------------------------|
| Found 1 1/2" OD galvanized pipe | South 8.2' |
| Nail & Tab in East face | 7" Elm N. 27 deg. E. 12.91' |
| Nail & Tab in South face | 10" Double Maple EAST 17.98' |
| Nail & Tab in East face | 6" Elm SOUTH 21.79' |
| Nail & Tab in South face | 12" Maple WEST 33.16' |

Signed by Randy B. Ligman Date 3/16/94
Surveyor's Michigan License No. 28413