

AUG 22 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'95 MAR 23 PM 4 09

For corners in ROSS TWP.
KALAMAZOO
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 1 S R9 W K-7
 T R
 T R
 T R
- 2. Property Controlling S T R
 in Section S T R
- 3. Miscellaneous S T R
 Property in Section S T R

James Jones
CLERK-REGISTER

LIBER 1 PG 1286

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen a field survey on February 2, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1825 - J. Mullet, D.S., Set Post
B. Oak 14" S. 65° E. 23 lks.
W. Oak 6" N. 33° E. 80 lks.

1883 - F. Hodgeman, C.S., Found stake & Stone & Stump of U.S. Witness.
Set 3' Earthen Post and Marked.
Hickory 8" S. 74½° E. 27½ lks.
Hickory 8" N. 21½° W. 30 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Clay Tile with Stones around it at intersection of fences N. S. E. & W., Found pipe at side of Tile.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
3/16/95 R.S.G.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Clay Tile is accepted as a careful and faithful perpetuation of the position of the original corner. Placed Standard sleeve over existing Clay Tile. Accessories:

- Nail & Tab (existing) in W. Face 10" Hickory N. 05° E. 10.68'
- Nail & Tab (existing) in N. Face 14" Hickory EAST 18.57'
- Nail & Tab (existing) in W. Face 14" Hickory SOUTH 11.68'
- Nail & Tab (existing) in S.W. Face 12" Hickory N. 45° W. 29.91'

Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 3/22/95