

SURVEY & REMONUMENTATION

JUL 23 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Ross Twp.
Kalamazoo
(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>1S.</u>	R	<u>9W.</u>	<u>K-8</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

LIBER 2 PAGE 133
97 MAY 16 PM 3 50
STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
CLERK - REGISTER
J. J. [Signature]

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
6. IWM Job No. 29369

I, Allen H. McMachen, in a field survey on April 1, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1825 - John Mullett, D.S.
Set quarter Section post, Aspen 8" N. 10° E. 333 lks.

1883 - F. Hodgman, C.S.
"Found stake standing in ditch at intersection of fences. Put 2' earthen post in bottom of ditch with stakes around and marked, Wh. Oak 16" N. 23° W. 283 lks."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found clay tile 4" below water in swamp. Place sleeve on tile and marked with orange post 2' West of tile.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
4-16-1997

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found clay tile is accepted a careful and faithful perpetuation of the position of the original corner. Placed Standard Sleeve over found clay tile, Accessories:

- Wood fence post N. 30° E. 3.95'
- Northeast corner High Voltage Steel Tower Base N. 40° W. 25.50'
- Southeast corner High Voltage Steel Tower Base N. 88° W. 15.86'
- Centerline High Voltage Steel Tower Line North ±10'



Signed by *Allen H. McMachen*
Surveyor's Michigan License No. 16935

Date 5/15/97