

SURVEY & REMONUMENTATION

7-
2-

JUL 23 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2 PAGE 125

For corners in Ross Twp.

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 1 S R 9 W	K-10
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 '97 APR 7 AM 9
 CLERK - REGISTER
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert E. Snell, in a field survey on July 9, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1826: United States Government Surveyors; set post.

Blk. Ash 12" N. 33° W. 25 lks.
 Blk. Ash 6" S. 43° E. 32 lks.

1883: F. Hodgman, County Surveyor; (6) "Found stake, stone, and bearing trees of re-survey standing, correct. Set 2' earthen post with 1 ft. of stone and brick beneath and stones around the top in marsh".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1969: Wilkins & Wheaton Engr. Co.; found tile in marsh - no witnesses.
 1996: Found 3" round tile with "x" on top.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 2-21-1997

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10: East 1/4 post, Section 26, T. 1 S., R. 9 W., ratified by the Kalamazoo County Remonumentation Program Peer Group on February 27, 1997 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found 3" round tile with "x" on top as set in a remonumentation survey in 1883 by F. Hodgman, County Surveyor. Placed remonumentation sleeve over.

PK Nail in 12" Ash N. 33° W. 16.50'
 PK Nail in 6" Ash S. 43° E. 21.12'
 PK Nail in 14" Maple N. 87° E. 38.94'
 PK Nail in 14" Beech S. 49° E. 50.16'

Signed by Robert E. Snell
 Surveyor's Michigan License No. 9734

Date 3-14-97