

**SURVEY &  
REMONUMENTATION**

FEB 18 1994

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

**COMMISSIONER LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970,

93 DEC 29 AM 10 31

For corners in

<u>Kalamazoo</u> (County)	Located In:	Corner Code #
<u>Ross Twp.</u>		
1. Public Land Survey	T <u>1 S</u> R <u>9 W</u>	<u>L-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*James E. Boynton*  
CLERK-REGISTER

LIBER **1** PG **1046**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, James E. Boynton, in a field survey on December 1, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Quarter post established by U.S. Government Deputy Surveyor John Mullett in 1826. Corner remonumented by F. Hodgeman in 1883, set standard tile, accessories: w.o. 6 N73E 17 1/2, w.o. 4 S. 22 1/2 W. 27 1/2. Corner found by Don Gilchrist in 1976, top tile broken - set mon. box over bottom tile.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found tile in mon. box from Gilchrist witnesses:  
24" Oak N. 88° W. 4.76'  
24" Oak N. 85° E. 10.99'  
10" Hickory N. 10° E. 15.30'

**RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
12-16-93**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found and accepted tile in mon. box as careful and faithful perpetuation of original corner. Set standard sleeve over tile, new witnesses: 2' N. of fence cor. 33" Oak West S. 25', 12" Hickory N. 25° W. 22.75', 12" Hickory N. 30° E. 15.00', 6" Cherry South 15.45'.

Signed by James E. Boynton Date 12-8-93  
Surveyor's Michigan License No. 29239