

SURVEY & REMONUMENTATION

FEB 26 1998

LIBER 2 PAGE 229

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'97 NOV 7 PM 3 38

Timothy Brown
CLERK - REGISTER

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Ross Twp.

Kalamazoo
(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>1S</u>	R	<u>9W</u>	<u>L-8</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		R
	S		T		R
3. Miscellaneous Property in Section	S		T		R
	S		T		R

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____
- 6. IWM Job No. 29369

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on April 2, 1997

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner not placed by original Government Surveyors.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Placed iron rod at intersection of quarter lines. All four quarter corners were previously ratified. An iron rod was found 9.0 feet South and 0.3 feet West of iron ~~placed~~ believed to have been set by Milton DeKeyser. P.S.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
9/10/97 *R.E.G.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

This position not established by original Government Surveyors. Placed iron rod is accepted as the best available evidence of the corner. Replaced iron rod with a 30" Harrison Monument, Accessories:

- Nail & Tab in North side of U. Pole N. 80° E. 43.26'
- Nail & Tab in North side of U. Pole S. 70° E. 61.10'
- Nail & Tab in Easterly side 6" Elm S. 20° W. 62.00'
- Nail & Tab in Easterly side 8" Oak North 56.30'



Signed by *Allen H. McMachen*

Date 11/5/97

Surveyor's Michigan License No. 16935