

SURVEY & REMONUMENTATION

JUL 23 1997

1
2
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Ross Twp.
Kalamazoo
(County)

Located In:

Corner Code #

- | | | | | | |
|--------------------------------------|---|------------|---|------------|------------|
| 1. Public Land Survey | T | <u>1S.</u> | R | <u>9W.</u> | <u>M-7</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Section | S | | T | R | |
| | S | | T | R | |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
6. IWM Job No. 29369

I, Allen H. McMachen, in a field survey on April 1, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1825 - John Mullett, D.S.
Set post corner to Sec. 13 & 24, Wh. Oak 17" S. 69½° W. 93 lks., Wh. Oak 16" N. 23° W. 95 lks.

1883 - F. Hodgman, C.S.
"Found iron and stone set for corner. Bearing trees gone. Residents say the corner is alright. Put 1' of coal and small stone at bottom and 2' earthen post over and marked. Bl. Oak 18" N. 22° W. 96 lks., Hickory 12" S. 17½° W. 71½ lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ½" iron in monument box, 8" long. Removed iron and excavated finding clay tile 1.2' below grade. Raised top section of tile and placed standard sleeve over. Measured North 54.5' to a pole barn spike (Bedford Twp. corner), Record gov't jog is 54.78'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found clay tile is accepted a careful and faithful perpetuation of the position of the original corner. Placed Standard Sleeve over found clay tile, Accessories:

- "PK" Nail in S.E. side utility pole N. 20° E. 84.94'
- 60d Nail & Tab in South side 22" Maple N. 80° E. 64.05'
- 60d Nail & Tab in South side 24" Maple N. 45° W. 41.19'
- 60d Nail & Tab in S.W. side 34" Tree S. 40° E. 54.04'

Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 5/15/97



R. EF

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
4-16-1997

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
.97 MAY 16 PM 3 50
CLERK - REGISTER
Annexed
LIBER 2PAGE 136
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												