

SURVEY & REMONUMENTATION

FEB 18 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'93 DEC 29 AM 10 31

For corners in

Kalamazoo

(County)

Ross Twp.

1. Public Land Survey

Located In:

Corner Code #

T 1 S R 9 W

M-9

T R

T R

T R

S T R

2. Property Controlling in Section

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

James E. Boynton
CLERK-REGISTER

LIBER

1 PG 1047

Register of Deeds Stamp & File Number

I, James E. Boynton, in a field survey on December 1, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by U.S. Government Deputy Surveyor John Mullett in 1826. Corner remonumented in 1883 by F. Hodgeman, set standard tile, accessories: w.o. 4 N. 23° W. 08, w.o. 3 S. 51° W. 05. Don Gilchrist found tile in 1976, LCRC filed 41, P. 643.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found tile from Gilchrist witnesses:

1' ± below surface

~~9" Elm S. 70° E. 9.55'~~

M SHD nail and cap in 8" Oak S. 40° W. 2.95'

16" Oak N. 30° W. 5.0'

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP

12-16-93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found and accepted tile as careful and faithful perpetuation of original corner. Set standard sleeve over tile, new witnesses: tile is 3' E. of N. & S. fence; 9" Elm S. 70° E. 9.55' to nail; 9" Basswood N. 65° E. 23.22' to nail; 20" Oak North 5.05' to nail; 10" Oak S. 60° W. 3.10' to nail.

Signed by James E. Boynton

Date 12-8-93

Surveyor's Michigan License No. 29239