

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 '95 SEP 25 PM 1 15

For corners in
 Kalamazoo

(County)	Located In:	Corner Code #
1. Public Land Survey	T 1 S. R 10 W.	A1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. <u>N/A</u> , Recorded Plat <u>N/A</u>		
5. Private Claims _____		

James [Signature]
 CLERK-REGISTER

LIBER 1 ■ 1352

Register of Deeds Stamp & File Number

I, GREGORY N. JENSEN, in a field survey on 10/4/94, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- a- SET POST 1826 GLO SURVEY - W.O., S 33 E, 82 LINKS (54.12')
- B.O., S 33 W, 43 LINKS (28.38')

F. HODGENAN COUNTY SURVEYOR - SET POST @ INTERSECTION OF FENCES N 33' W, 82 LINKS (54.12') FROM STUMP OF WHITE OAK.
 HICK. 12", S 7' E, 14.5 LINKS (9.57')
 HICK. 10", S 64' W, 22 LINKS (14.52')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- b- A1
 FOUND SOLID CLAY TILE W/ CROSS AT INTERSECTION OF OLD WOVEN WIRE FENCES. (NO BEARING TREES STANDING)

RATIFIED
 BY KALAMAZOO COUNTY
 REMONUMENTATION
 PEER GROUP

7-23-95
 8-10-95 J.C.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- c- A1 NORTHWEST 1/4 SECTION 6, T.1 S., R.10 W., RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PROGRAM PEER GROUP ON JULY 23, 1995. FOUND CLAY TILE CALLED FOR BY F. HODGENAN COUNTY SURVEYOR AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER. PLACED REMONUMENTATION SLEEVE OVER TILE.

- 6" WILD CHERRY S 50' E, 22.6'
- 40" OAK WEST, 38.5'
- 6" SASSAFRAS S 5' E, 14.6'
- 12" SASSAFRAS N 50' E, 10.96'

Signed by Gregory N. Jensen
 Surveyor's Michigan License No. 31593

Date 9/11/95

