

FEB 08 1999 LIBER

2 PAGE 410

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
98 DEC 23 AM 3 05
CLERK - REGISTER

| | | |
|------------------------------------|-------------|--------------|
| Kalamazoo | Located In: | Corner Code# |
| (County) | | |
| Richland Township | | |
| 1. Public Land Survey | T 1S R 10W | A-7 |
| | T R | |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Gary D. Hahn, in a field survey on April 29, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1827 - Established by U.S. Deputy Surveyor John Mullett - "Int. w. boundary 64 lks. N of post. Set post at int. cor. to secs. 18 & 19." Wh. Oak 10" S 65 E 40 lks. Wh. Oak 16" N 40 E 60 lks.

1887 - F. Hodgman - "Found rotten stake 64 lks north of cor. of sec. 13 & 24 Cooper. Set post. Wh. Oak 8" N 27 1/2 E 19 1/2 lks. Y. Oak 8" S 29 E 42 lks.

1902 - E. Strong - Tile - Cherry 8" East 19

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998 - Original monument and accessories not recovered. Found 1/2" rebar below asphalt road. Found two 1" dia. x 22" long rods side by side directly over clay tile. Tile is 6.8' below road surface. Tile is 0.06' S. and 2.51' W. of 1/2" rod. Left both 1" dia. rods over tile.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7, Northwest Corner Section 19, Town 1 South, Range 12 West, ratified by Kalamazoo County Remonumentation Peer Group on May 21, 1998. Position of the 1/2" rebar is accepted as a careful and faithful perpetuation of the position of the original corner. Set 30" Harrison Monument in a Monument Box directly over tile.

Witness Ties:

- Fnd. 10d Nail in 34" Oak N 30 W 71.02'
- Fnd. P.K. Nail in P.P. N 18 E 34.82'
- Set P.K. Nail in 10" Hickory N 85 W 83.01'
- Set 1/2" rebar at b/curb east 13.65'
- Harrison monument in mon. box (NE Cor. Sec. 24, T. 1 S., R. 11 W.) South 42.17'

Signed by [Signature]
Surveyor's Michigan License No. 38116

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
5/21/98



Date 12/08/98
FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS,
JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983 REVISED OCT., 1995