

OCT 06 1997

COMMISSION

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'97 AUG 21 PM 3 49

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Smith & Smith
CLERK - REGISTER

For corners in Richland Twp.
Kalamazoo
(County)

Located In: Corner Code #

- | | | | | | |
|--------------------------------------|---|-----|---|------|-----|
| 1. Public Land Survey | T | 1S. | R | 10W. | A-8 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | T | R | | |
| | S | T | R | | |
| 3. Miscellaneous Property in Section | S | T | R | | |
| | S | T | R | | |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

LIBER 2PAGE 188

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on June 2, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner not set by original Government Survey
1902 - Ed Strong, C.S., "Found with 'X' also stone for Cooper", Y. Oak 8" N. 20' W. 15 lks.

1973 - Smith & Smith, Inc., "Found stone w/"X" from old wits and jog distance from Cooper corner R.=40.92 M.=40.66', Stone is 12'± Southerly from centerline dirt drive, 12" Oak S. 70° E. 22.29' to nail, 14" Tw. Oak S. 15° W. 19.00' to nail, 14" Tw. Maple N. 05° W. 41.43' to nail, Stone is 40.66' North of Cooper corner."

1973 - Ingersoll, Watson & McMachen, Inc., "Found stone w/"X" per 1973 S. & S. witnesses.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Intersected 1973 witnesses and found stone to be graded out. Set standard marker at intersection of witnesses and from previous traverse points in area.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
6-19-1997

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Position of stone per 1973 witnesses is accepted as a careful and faithful perpetuation of the position of the original corner. Placed standard Harrison Monument, Accessories:

- Nail & Tab in 20" Tw. Maple N. 5° W. 40.54'
- Nail & Tab in 14" Oak N. 60° E. 73.64'
- Nail & Tab in 18" Oak S. 70° E. 23.17'
- Nail & Tab in 20" Tw. Oak S. 15° W. 18.90'



Signed by *Allen H. McMachen*

Date 8/20/97

Surveyor's Michigan License No. 16935