

SURVEY & REMONUMENTATION

FEB 26 1998

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

LIBER 2 PAGE 227
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

'97 NOV 7 PM 3 38

SECTION
Richland Twp.
For corners in Kalamazoo
(County)

Located In: Corner Code #

Smith Brown

CLERK - REGISTER

1. Public Land Survey	T	1S.	R	10W.	A-10
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

6. IWM Job No. 26019

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on June 14, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner not set by original Government Surveyors

RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP

9/10/97

R.E.S.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron rod 28.15 feet North of found axle shaft at East quarter corner, Section 25, Cooper Township. The mean of G.L.O. notes jogs is 28.05 feet. Removed iron and dug to depth of 4 feet finding no additional evidence of corner. Measured South to pointed stone at Southwest corner at 2643.3 and measured East to 1 1/2" pipe at Center quarter corner at 2265.84 feet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 1/2" iron rod is accepted as the best available evidence of the position of the corner. Replaced iron with a 30" Harrison Monument, Accessories:

- Nail & Tab in West side of 12" Oak N. 20° E. 17.75'
- Nail & Tab in East side of 12" Cherry N. 72° E. 23.20'
- Nail & Tab in North side 24" Oak S. 30° W. 21.30'
- Nail & Tab in 8" Cherry N. 60° W. 37.96'



Signed by *Allen H. McMachen*

Date 10/28/97

Surveyor's Michigan License No. 16935