

**SURVEY & REMONUMENTATION**

NOV 25 1998

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**

**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Richland Twp.  
Kalamazoo  
(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>1S.</u>	R	<u>10W.</u>	<u>B-7</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

IWM Job No. 30481

I, Allen H. McMachen, in a field survey on March 26, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1827 - John Mullett, D.S., Set quarter Section post, Tam 15" S. 50° W. 14 lks., Tam 12" S. 82° E., 32 lks. (notes indicate 34.55 chains between N.W. cor. & N¼ cor.).
- 1887 - F. Hodgman, C.S., "Found stake in marsh N. 82° W. from stump of one bearing & N. 50° E. 14 lks. from the stump of the other. Set post 10½ lks. N.W. from North rail of railroad. Oak in South margin of bank S.W. 149½ lks."
- 1902 - Ed Strong, C.S., "Tile buried by filling of railroad, set stone over. B. Oak 4" N. 02° W., 45 lks, rail about 6 feet East, (Strong's map indicates a 'surplus of 13 lks.' between N.W. cor. & N¼ cor. & divided equally into ¼ miles) Map also shows measure from N¼ cor. West to 1/8 cor. is 20.06½ chains, (1324.29)."

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found iron rod 2288.54 feet East of a surface marker at N.W. corner, Section 19. Dug under said iron to depth of 3.5' finding no additional evidence of corner. Property owner in area shared that in the early '70's the railroad company reworked the tracks between the two creek crossings with dozers and placed fill. Tile believed to have been removed during this excavation. All accessories to tile are now gone. It appears that the found iron was placed by an unknown surveyor at Strong's distance of 2288.88 feet (34.55 ch. [gov't] + 13 lks. [Strong's surplus]) from a surface marker at N.W. cor.. N.W. corner was investigated and true historic marker (tile) was found to be 2.51 feet West and 0.06 feet South of surface marker. Placed 30" Harrison Monument at Ed Strong's 1902 measure of 2288.88 feet East from tile found at N.W. cor. and on line between N.W. cor. (tile) and the N.E. cor. (Harrison monument).

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.**

Position of 30" Harrison Monument placed is accepted as a careful and faithful re-establishment of the position of the corner,  
Accessories:

- 60d Nail in West side of Triple 6" Elm N. 30° E. 4.50'
- Nail in 4" Maple S. 57° E. 27.89'
- 60d Nail in S.W. side of 8" Elm S. 35° W. 53.72'
- 60d Nail in South side of 6" Oak N. 85° E. 30.97'
- ½" iron rod N. 60° E. 2.51'

Signed by Allen H. McMachen  
Surveyor's Michigan License No. 16935



Date 7/14/98

LIBER 2 PAGE 330  
STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
98 OCT 12 PM 1 29  
CLERK - REGISTER  
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7	●											
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												