

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in RICHLAND TWP
KALAMAZOO
(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>1S.</u>	R	<u>10W.</u>	<u>B-8</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

LIBER 2 PAGE 331
CLERK - REGISTER
98 OCT 12 PM 1 29
STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
6. IWM Job No. 30481

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on March 26, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner not placed by original government surveyors.

1902 - Ed Strong, C.S., "Found stone by Albertson on West side of fence & in fence going West."

1940 - Wilkins & Wheaton, Survey in SW $\frac{1}{4}$, Sec19 shows meas. between tile @ S $\frac{1}{4}$ cor. North to the 1/8 cor. (stone with "X") at 1319.81'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found stone at 1317.94' North of found stone with "X" at the 1940 1/8 corner. Measure from tile @ S $\frac{1}{4}$ corner North to 1940 1/8 corner is 1318.13'. A straight line from tile at S $\frac{1}{4}$ corner to the Harrison Monument at the N $\frac{1}{4}$ cor. is 0.7' East of found stone at C $\frac{1}{4}$ cor..

SURVEY & REMONUMENTATION

NOV 25 1998

SECTION

RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP
5/21/98 R.E.C.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

This position not established by original government surveyors. Found stone is accepted as the best available evidence of the position of the corner. Dug around stone and found it was too large to remove (16" X 16" X 24" high) from hole. Enlarged hole to South and rolled stone on its side to South and placed 30" Harrison Monument at original position of stone, Accessories:

- Nail in South side 6" Oak S. 35° W. 20.28'
- Nail in SW side 16" Oak N. 63° W. 2.73'
- Nail (±4' above grade) in NW side 24" Oak N. 10° E. 17.05'
- Nail in North side 14" Oak S. 61° E. 13.15'



Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 10/9/98