

7  
u

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Richland Twp.  
Kalamazoo  
(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>1S.</u>	R	<u>10W.</u>	<u>B-9</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_  
6. IWM JOB No. 30481

I, Allen H. McMachen, in a field survey on March 16, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1827 - John Mullett, D.S., Set quarter Section post, Wh. Oak 15" N. 81° E. 34 lks., Wh. Oak 18" N. 46° W., 31 lks..
- 1887 - F. Hodgman, C.S., "Found big stone S. 46° E. 31 lks. from stump of bearing tree marked plain. Set post under the stone, Hickory 6" S. 30° W. 48½ lks., Y. Oak 10" N. 41° E. 48 lks..

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found ½" iron in Mon. Box. Removed ½" iron and bored inside box finding clay tile 29" below road surface. Found clay tile is 0.04' South and 0.08' West of surface marker.

**SURVEY & REMONUMENTATION**  
**NOV 25 1998**  
**SECTION**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Found tile is accepted as a careful and faithful perpetuation of the position of the original corner. Placed 20" Harrison Monument over tile, Accessories:

- Nail & Tab in East side 16" Oak North 28.32'
- Nail & Tab in South side 16" Oak N. 73° E. 66.26'
- Nail & Tab in Northeasterly side 26" Oak S. 50° E. 43.54'
- Nail & Tab in Southeasterly side 6" Oak S. 53° W. 55.88'

Signed by Allen H. McMachen  
Surveyor's Michigan License No. 16935



Date 4/29/98

LIBER 2 PAGE 332  
98 OCT 12 PM 1 29  
CLERK - REGISTER  
STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												