

SURVEY & REMONUMENTATION

SEP 14 1998

LIBER 2 PAGE 285

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in Richland Twp. Kalamazoo (County)

Located In:

Corner Code #

1. Public Land Survey	T	1S.	R	10W.	B-12
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
1998 FEB 5 PM 3 49
Clerk - Register
Janice J. Howard

Register of Deeds Stamp & File Number

I, Allen H. McMachen, in a field survey on November 10, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner not placed by original government surveyors.

1905 - E. Strong, C.S., "By Albertson" Hickory 6" S. 38° E. 80 lks..

1930 - Origin Unknown, Stone 3' below, Hickory S. 38° E. 52.45' (face), 0.5' North of fence East, Hickory East 31.3' (face).

1971 - Ingersoll, Watson & McMachen, Inc., Found iron rod, 20" Hickory S.E. 53.30', Tw. 15" Hickory East 31.81', 3" dia. metal fence post N.W. 42.25'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron rod in monument box. Dug under iron and found pointed stone directly below with ring of small stones around. Pointed stone is 3' below road surface, removed stone & found nothing under.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found pointed stone is accepted as the best available evidence of the position of the original corner. Placed Harrison Monument over pointed stone with monument box over, Accessories:

Iron rod placed N. 45° E. 27.97'

Iron rod placed S. 45° W. 45.76'

Iron rod placed N. 50° W. 47.09'

"PK" Nail (existing) in SW side of U. Pole S. 25° E. 77.07'

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
12/10/97 *R.E.S.*



Signed by *Allen H. McMachen*
Surveyor's Michigan License No. 16935

Date 1/19/98