

SURVEY & REMONUMENTATION

JUL 23 1997

1
2
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Richland Twp.
Kalamazoo
(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>1S.</u>	R	<u>10W.</u>	<u>C-8</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

LIBER 2 PAGE 130

CLERK - REGISTER

Handwritten signature

97 MAY 16 PM 3 49

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
6. IWM Job No. 26689

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Allen H. McMachen, in a field survey on March 17, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1827 - John Mullett, D.S., Set 1/4 Section post, Wh. Oak 10" S. 47° E. 14 lks., Y. Oak 14" N. 31° W. 20 lks.

1887 - F. Hodgman, C.S., "Found stake with earthenware around, bearing trees of resurvey standing, set post"

1973 - Smith & Smith, Inc., "Had 1894 & 1891 Witnesses, both called for Hickory East 35 1/2 lks., All other old witness trees are gone, Dug large hole and could not find any signs, possible road construction in area, found 2' - 3' of fill and dug 2' into natural soil, Set 3/4" iron bar 18" long from 12" Hickory (now 26") witness tree, 12" Hickory East 35 1/2 lks. (23.43'), Wits: 3/4" iron bar, Iron is 2.5' E. of centerline road North, Iron is 4.2' North of centerline road West, 26" Hickory East, 23.68 feet to nail, 20" Triple Hickory S. 05° E. 4.89 feet to nail, 10" Hickory N. 40° E. 40.74' to nail

1973 - Ingersoll, Watson & McMachen, Inc., Found 3/4" iron, measured North 2643.05', measured South 2648.12', measured West 2655.50'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" iron rod. Area appeared to have already been cut down for driveway to East. Excavated area 6' X 5' around found iron to a depth of 4' and found no additional evidence of marker. Measured North 2642.96' to N.W. cor., Measured South 2648.31 feet to S.W. cor., Measured East 2615.68 feet to intersection of 1/4 lines and continued East 2623.11 feet to E 1/4 cor. (Total = 5238.79').

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
4-16-1997**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 1" iron is accepted as the best available evidence of the position of the original corner. Replaced 1" iron with a Standard Harrison Monument, Accessories:

- Nail & Tab in N.W. side 14" Hickory N. 30° E. 40.37'
- Nail & Tab in N. side 20" Hickory East 24.34'
- Nail & Tab in N.E. side 14" Hickory S. 40° E. 6.43'
- Nail & Tab in S. side 18" Hickory N. 85° W. 156.72'



Handwritten initials R.E.F.

Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 5/15/97