

LAND CORNER RECORDATION CERTIFICATE, 94 APR 28 AM 9 11
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALAMAZOO
(County)

Located in:

Corner Code #

Sec. 30, Richland Twp.

1. Public Land Survey

T 1 S R 10 W

C-10

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
 in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
 Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

James J. [Signature]

CLERK-REGISTER

LIBER 1 PG 1138

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on March 1, 19 94,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	10	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1826-Original corner placed by U.S. Government. Survey-Set ¼ Section Post.

Wh. Oak 30" North 77° West 10 Lks

Wh. Oak 12" North 80° East 40 Lks

1887-F.Hodgeman, County Surveyor-Found stake with stone around and stump of Bearing Trees in place. Set Post.

Wh. Oak 30" South 85° East 49 Lks

Wh. Oak 3" South 27° East 8½ Lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3" round tile near surface from 1972 LCRC witness.

R. E. Snell
RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 4-21-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-10 East ¼ Post Section 30, T. 1 S., R. 10 W., ratified by Kalamazoo County Remonumentation Program Peer Group on April 21, 1994. Found 3" round tile, stones around near surface, as called for in 1887 remonumentation survey by F.Hodgeman and is accepted as a careful and faithful perpetuation of the original corner's position. Placed remonumentation sleeve over tile.

- PK Nail in South Side 18" Oak North 70° West 34.05'
- PK Nail in East Side 20" Oak North 18° East 19.98'
- PK Nail in East Side 26" Oak South 09° West 9.99'
- PK Nail in East Side 18" Oak South 04° West 19.42'
- 1" Pipe West 0.30'

Signed by

Robert E. Snell

Date

4-26-94

Surveyor's Michigan License No.

9734