

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

APR 28 AM 9 11

For corners in

KALAMAZOO

(County)

Located In:

Corner Code #

Sec. 17, Richland

1. Public Land Survey

T 1 S R 10 W

D-7

T R

T R

T R

2. Property Controlling
 in Section

S T R

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

James E. Jones

CLERK - REGISTER

LIBER 1 PG 1137

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7		●											
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert E. Snell, in a field survey on January 12, 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826-Original corner established by U.S. Government Survey-Set $\frac{1}{4}$ Post.

Wh. oak 18" South 30° East 35 Lks

Wh. Oak 18' North 13° East 68 Lks

1870-F.Hodgeman, County Surveyor-found stone of resurvey.

1877-F.Hodgeman, County Surveyor-found stone of resurvey at angle of road-Set Post.

Hickory 6" South 46° East 63 $\frac{1}{2}$ Lks

Wh. Oak 8" South 06° West 60 Lks

1993-Wilkins & Wheaton Engineering Co.-Found tile down 6" with stone around in line with CL of

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: road East and North

Found 3" round tile with "X" on top with stone around, down 6".

R. E. Snell
RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
 3-3-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-7 South $\frac{1}{4}$ Post Section 17, T. 1 S., R. 10 W., ratified by Kalamazoo County Remonumentation Program Peer Group on March 3, 1994. Found 3" round tile with "X" on top and stone around as called for in 1877 remonumentation survey by F.Hodgeman and is accepted as a careful and faithful perpetuation of the original corner's position. Placed remonumentation sleeve over top of tile.

PK Nail in West Side	12" Elm	South 12° East	8.69'
PK Nail in North Side	18" Oak	South 60° East	71.04'
PK Nail in Northwest Side	Power Pole	South 65° West	80.86'
SE Corner of 12"x12" Concrete Fence Post	West		25.79'

Signed by

Robert E. Snell

Date

4-26-94

Surveyor's Michigan License No.

9734