

OCT 06 1997

LIBER 2 PAGE 198

7 COMMISSION

2

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Richland Twp.
Kalamazoo
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey	T	<u>1S.</u>	R	<u>10W.</u>	<u>D-8</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
1997 SEP 5 PM 3 42
J. J. [Signature]
CLERK - REGISTER

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____
- 6. IWM Job No. 26689

I, Allen H. McMachen, in a field survey on June 12, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner not placed by original Government Surveyors. No historic information was found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No marker was found occupying the Center quarter corner position. Placed Harrison Monument at intersection of quarter lines. All four exterior quarter corners were already ratified. Corner is within Unit 12 of "Southworth Farms" site condominium.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP

4/17/97 [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

This position not established by original Government Surveyors. Harrison Monument placed at intersection of quarter lines is accepted as the best available evidence of the position of the corner. Accessories:

- Iron rod with IWM cap at intersection of North line Unit 12, "Southworth Farms" condominium and the North and South quarter line N. 0° 29' 29" E. 233.84'
- Iron rod with IWM cap at intersection of South line Unit 12, "Southworth Farms" condominium and the North and South quarter line S. 0° 29' 29" W. 330.86'
- Iron rod with IWM cap at intersection of East line Unit 12, "Southworth Farms" condominium and the East and West quarter line S. 88° 10' 33" E. 313.64'
- Iron rod with IWM cap at intersection of West line Unit 12, "Southworth Farms" condominium and the East and West quarter line N. 88° 10' 33" E. 86.45'



Signed by [Signature]
Surveyor's Michigan License No. 16935

Date 8/25/97