

1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

'95 AUG 25 PM 3 51

For corners in

Kalamazoo

(County)

Located In:

Corner Code #/

Richland Township

1. Public Land Survey

T 1 S R 10 W

D-12

2. Property Controlling in Section

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

[Signature]

CLERK-REGISTER

LIBER

1 1332

Register of Deeds Stamp & File Number

I, Robert E. Snell, in a field survey on September 6, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. Cell 12D contains a circled '32'.

A. Description of original monument and accessories and/or subsequent restoration: Original Corner Not Set By Original Government Surveyors.

1874: Ed Strong, County Surveyor; Found stone and stake by Pratt (surveyor) and side stone 50 Lks West.

1874: F. Hodgman, Surveyor; Center 1/4, Stone by Strong in place of a stake by former survey one way correct.

1887: F. Hodgman, County Surveyor; Center 1/4 Set on former survey.

1950: Wilkins & Wheaton Engineering; Found stone by Strong, 165' South of Center 1/4 Post and placed iron at Center 1/4 Post.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found iron, side stone and plat monument. Drill stone 32.45' West and plat monument 50.0' West of Center 1/4 Post.

RATIFIED BY KALAMAZOO COUNTY REMONUMENTATION PEER GROUP 5-18-95 [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-12 Center 1/4 Post Section 32, T. 1 S., R. 10 W., Ratified by the Kalamazoo County Remonumentation Program Peer Group on May 18, 1995 and is accepted as the best available evidence of the position of the corner. This position not established by original government surveyors. Found iron in Centerline Road and a drill stone 32.45' West. Removed iron and placed a 20" Harrison monument and monument box in its place.

- PK Nail in Northwest Side 15" Double Wild Cherry North 60° East 31.74'
PK Nail in North Side 26" Wild Cherry South 88° East 27.76'
PK Nail in South Side 24" Wild Cherry North 88° West 53.01'
PK Nail in West Side 24" Wild Cherry North 18° West 66.16'
Centerline of 27th Street West 2.6'

Signed by [Signature]

Date 8.22.95

Surveyor's Michigan License No. 9734