

1,
2
SURVEY &
REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD

FEB 18 1994 LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

'94 JAN 25 PM 1 51

For corners in **COMMISSION**

Kalamazoo Located In: Corner Code #
(County)

- | | | |
|------------------------------------|----------------------------|------------|
| 1. Public Land Survey | T <u>1</u> S R <u>10</u> W | <u>E-3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Jamail Young
CLERK-REGISTER

LIBER 1 PG 1098

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Gregory N. Jensen, in a field survey on May 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set post corner to Section 4, 5, 8 & 9.

Wh. Oak 18" N 70° E, 64 Lks. (42.24')

Wh. Oak 18" N 10° W, 64 Lks. (42.24')

By original government survey by John Mullett, 1826.

1887-F. Hodgeman County Surveyor

Found stake S 10° E, 64 Lks. from Bearing Tree Standing Set Post.

Post Wh. Oak 18" N 58° E, 53 Lks. (34.98')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found solid clay tile w/cross an intersection of old down fences flush with surface.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
8-19-93**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-3 Southwest corner Section 4, T. 1 S., R. 10 W., Ratified by Kalamazoo County Remonumentation Program Peer Group on August 19, 1993. Found clay tile called for in 1887 survey by F. Hodgeman and is accepted as a careful and faithful perpetuation of the position of the original corner. Placed remonumentation spike over tile.

- Spike in root of 16" Oak N 45° E, 39.06'
- Spike in root of 16" Oak S 45° E, 36.35'
- Spike in root of 20" Map. S 20° W, 16.90'
- Spike in root of 6" Oak N 30° W, 10.60'



Signed by Gregory N. Jensen
Surveyor's Michigan License No. 31593

Date January 25, 1994