

SURVEY & REMONUMENTATION

JUL 23 1997

COMMISSION

LIBER 2 PAGE 129

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Richland Twp.
Kalamazoo
(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>1S.</u>	R	<u>10W.</u>	<u>E-9</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

STATE OF MICHIGAN
 COUNTY OF KALAMAZOO
 RECEIVED FOR RECORD
 '97 MAY 16 PM 3 49
 J. E. S.
 CLERK - REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
6. IWM Job No. 26689

I, Allen H. McMachen, in a field survey on March 31, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1827 - John Mullett, D.S.
Set post corner to Sec. 20, 21, 28 & 29
Wh. Oak 36" N. 80° W. 12 lks.
Y. Oak 10" N. 46° E. 29 lks.

1887 - F. Hodgman, C.S.
"Found stake and stones in place and bearing trees of resurvey standing. Set post"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron rod in monument box. Removed iron and excavated inside box and found clay tile directly under iron rod, 1' below grade.

**RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
4-16-1997**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found clay tile is accepted a careful and faithful perpetuation of the position of the original corner. Placed Standard Sleeve over found clay tile, Accessories:

- "PK" Nail in West side Twin 8" Elm N. 25° E. 102.23'
- "PK" Nail in Easterly side 30" Chestnut S. 40° W. 60.06'
- "PK" Nail in N.E. side 16" Locust N. 35° W. 41.61'
- Nail & Tab (found) in Northerly side Utility Pole S. 60° E. 53.70'



Signed by Allen H. McMachen
Surveyor's Michigan License No. 16935

Date 5/15/97