

SURVEY & REMONUMENTATION

MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

CLERK - REGISTER

LIBER

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORD
96 AUG 26 PM 4 01

2 PAGE 051

Register of Deeds Stamp & File Number

For corners in

Kalamazoo
(County)

Located in:

Corner Code #

Richland
1. Public Land Survey

T 1S	R 10W	E-12
T	R	
T	R	
T	R	
S	T	R
S	T	R
S	T	R
S	T	R

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Snell, in a field survey on May 3, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

RATIFIED
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP 7/18/1996

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration.
1826: United States Government surveyors; set 1/4 section post
Wh. Oak 9" N 33° W 27 lks.
Wh. Oak 12" S 55° E 20 lks.

1887: F. Hodgman, County Surveyor; found stone in place and bearing trees of former survey standing. Set post with stone around.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.
1952: Michigan State Highway Dept. found 5/8" iron bar over tile 115.55' South of centerline M-43 Hwy.

1966: Wilkins and Wheaton Engr. Co.; replaced iron bar and tile with plat monument for Upjohn Co.

1996: Found plat monument in monument box 115.50' South of centerline M-43 Hwy.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.
E-12: West 1/4 post Section 33, T 1 S, R 10 W; ratified by the Kalamazoo County Remonumentation Program Peer Group on July 18, 1996 and is accepted as a careful and faithful perpetuation of the position of the original corner. Found plat monument. Placed 10" of Harrison monument in concrete in monument box.
PK nail on East side Power Pole N 26° W 22.64'
PK nail on West side Telephone Pole N 44° E 52.97'
PK nail on East side 32" Hickory S 10° E 87.01'
PK nail on West side Wood Fence Post S 32° W 102.11'

Signed by Robert E. Snell
Surveyor's Michigan License No. 9734

Date 8-22-1996